ENG 2024-01: 2024 Resurfacing Project Information Sheet

*** Meadow Woods Subdivision ***

<u>Meadowood Circle – 0.07 Miles – 22' wide – Beginning at CR 974 (Eastridge Drive) Ending at Dead End</u>

- Bituminous tack coat before each lift
- Leveling 80lbs OGI
- Topping 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4" wide once after leveling
- Temporary centerline stripe 4" wide once after topping
- Permanent centerline stripe 5" wide 15 days after topping
- 1 Stop Bar (24" Thermoplastic)

<u>Springbrook Drive – 0.28 Miles – 22' wide – Beginning at CR 974 (Eastridge Drive) Ending at Dead End</u>

- Bituminous tack coat before each lift
- Leveling 80lbs OGI
- Topping 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4" wide once after leveling
- Temporary centerline stripe 4" wide once after topping
- Permanent centerline stripe 5" wide 15 days after topping
- 1 Stop Bar (24" Thermoplastic)

<u>Summer Field Drive – 0.29 Miles – 22' wide – Beginning at CR 868 (Old US Hwy 41) Ending at CR 968 (Springbrook Drive)</u>

- Bituminous tack coat before each lift
- Leveling 80lbs OGI
- Topping 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4" wide once after leveling
- Temporary centerline stripe 4" wide once after topping
- Permanent centerline stripe 5" wide 15 days after topping
- 1 Stop Bar (24" Thermoplastic)