

ENG 2025-01: 2025 Resurfacing
Project Information Sheet

***** Hillside Subdivision *****

Eastview Drive – 0.12 Miles – 22' wide – Beginning at Hill Top Drive Ending at Meadowdale Drive

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4" wide – once after leveling
- Temporary centerline and edge line stripe 4" wide – once after topping
- Permanent centerline and edge line stripe 5" wide – 15 days after topping
- 2 Stop Bars (24" Thermoplastic)

Hill Top Drive – 0.20 Miles – 22' wide – Beginning at Johnson Hill Drive Ending at Johnson Road SE

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4" wide – once after leveling
- Temporary centerline and edge line stripe 4" wide – once after topping
- Permanent centerline and edge line stripe 5" wide – 15 days after topping
- 2 Stop Bars (24" Thermoplastic)

Hillway Drive – 0.20 Miles – 23' wide – Beginning at Meadowdale Drive Ending at M D Guess Road

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4" wide – once after leveling
- Temporary centerline and edge line stripe 4" wide – once after topping
- Permanent centerline and edge line stripe 5" wide – 15 days after topping
- 2 Stop Bars (24" Thermoplastic)